



SREE NARAYANA GURUKULAM CHARITABLE TRUST

PERUMBAVOOR, ERNAKULAM DIST., KERALA - 683 542.

PH: Trust Office 0484 - 2594885, SNDP Union: 2592585, 2522585, College 0484 - 2760887, 2764841 FAX: 0484 2762541

E-mail - sngtrust@yahoo.co.in

Reg. No.133/IV/2001

(AN UNDERTAKING OF KUNNATHUNADU S.N.D.P. UNION)

PRESIDENT
K.K. Karnan
0484-2462422
98469 00000

VICE PRESIDENT
Suresh Bharathan
0484-2426995
98470 37371

SECRETARY
M.K. Viswanathan
0484-2524110
94470 29830

JOINT SECRETARY
T.V. Padman
0484-2760823
94478 16464

TREASURER
A.B. Jayaprakash
0484-2451637
98472 75220

No: SNGCT/13/12

12.03.2012

To

Mr. PMK Moorthy,
Director, Transdot Pvt Ltd,
C - 10, "Kuttikkatt" Jawahar Nagar,
Thiruvananthapuram, Pin 695 003.

Sir,

Sub: Work order for Bio gas plant for SNG College of Engineering - issuing

Ref: Your Quotation dt 07.03.2012

Work order for the Bio gas plant at SNG College of Engineering, Kadayiruppu as per your quotation is hereby issued. We agree to fix the final price at Rs.435000 (Rupees four lakhs thirty five thousand only), You are requested to complete the work immediately.

Yours faith fully



[Signature]
SECRETARY

Sree Narayana Gurukulam Charitable Trust
Perumbavoor - 683 542



[Signature]
PRINCIPAL
Sree Narayana Gurukulam
College of Engineering
Kadayiruppu, Kolenchery - 682 311

Transdot

TRANSDOT PRIVATE LIMITED
C-10, "KUTTIKATT", JAWAHAR NAGAR
THIRUVANANTHAPURAM - 695 003, INDIA
TEL: 91 471 2723608, FAX: 91 471 2726838
E-mail: transdot@transdot.net

The Secretary

7th March 2012

Sree Narayana Gurukulam Charitable Trust

SNDP Union shopping Complex, Perumbavoor PO

Pincode 683542

Sir

We are giving our best price for the bio- plant at Kadayirrupa college as below: -

01. Water proof base concrete
02. Air tight doom with inner and outer plastering
03. Two coats of black paint on the inner doom surface

A Hydraulic tank of 3mx3mx2m

A Inlet tank of 0.6mx0.6m/1.2m.

1" SS Nipple with ball valve at the top of the doom for gas collection **Rs.4, 35,000.00**

(Rs.Four lakhs thirty five thousand only)

Taxes: Inclusive

Payment: 60% advance and 40% after completion of work.

In case you require any further clarification, please feel free to contact us.

Thanking You

Yours Sincerely

For TRANSDOT PRIVATE LTD

ANANDAKUMAR.R

GENERAL MANAGER

Mob. 9048306374



R. Hase
PRINCIPAL
Sree Narayana Gurukulam
College of Engineering
Kadayiruppu, Kolenchery-682 311

AGREEMENT FOR CONSTRUCTION OF SWEAGE TREATMENT PLANT (90 KL) FOR LADIES HOSTEL AND MAIN BLOCK FOR SREE NARAYANA GURUKULAM COLLEGE OF ENGINEERING, KADAYIRUPPU (CIVIL WORK ONLY)

SCHEDULE OF WORK

Sl.No.	Quantity	Unit	Specification	Unit	Rate	Amount
1.01	300.00	m2	Clearing grass and other over growths of vegetation and small trees of girth up to 30cm including rooting out and removal of rubbish up to a distance of 150m out side the periphery of the area cleared	/100m2	132.00	396.00
1.02	1150.00	m3	Earthwork excavation for the concrete tank with working area around	/m3	200.00	230000.00
1.03	480.00	hours	Bailing out water using 5 HP engine and pump set including conveyance the same to the site erecting charges etc.complete.	/hour	169.84	81523.20
1.04	24.00	m3	Cement concrete 1:4:8 using 40mm (nominal size) broken stones. (unit m3)	/m3	3293.30	79039.20
1.05	12.00	m3	Reinforced cement concrete M20 mix using 20mm nominal broken stones for septic tank bottom beam including all formwork, watering, curing etc complete but excluding the cost of reinforcement. [unit	/10 dm3	95.00	114000.00
1.06	60.00	m3	Reinforced cement concrete M20 mix using 20mm nominal broken stones for septic tank bottom slab including all formwork, watering, curing etc complete but excluding the cost of reinforcement. [unit	/10 dm3	52.00	312000.00
1.07	80.00	m3	Reinforced cement concrete M20 mix using 20mm nominal broken stones for slabs and tank inside wall including all formwork, watering, curing etc complete but excluding the cost of reinforcement after sinking the tank	/10 dm3	110.00	880000.00
1.08	40	m3	Brick work in cm 1:5 with country burnt bricks 19x 9 x 9 cms for partition wall including cost , conveyance and labour charge etc complete.	/m3	4099.22	163968.80
1.09	44.00	m3	Reinforced cement concrete M20 mix using 20mm nominal broken stones for cover slab including all formwork, watering, curing etc complete but excluding the cost of reinforcement.	/10 dm3	76.00	334400.00
1.10	200.00	qntl	Reinforcement for R.C.C works bend, tied and placed in position (plain grill requiring bending cold) using Torsteel.	/qntl	4570.72	914144.00
1.11	1050.00	m2	Plastering with cement mortar 1:3, 9mm thick, one coat, floated hard and trowelled smooth	/10m2	1200.97	126101.85



College of Engineering
Kadayiruppu, Kodayichery-682 311

[Handwritten Signature]
SECRETARY
Sree Narayana Gurukulam Charitable Trust
Perumbavoor-683 542

1.12	2.00	m3	Supplying and filling 40 mm metal for sludge drying bed 1 & 2 including cost of material, labour for filling conveyance etc complete.	/m3	739.20	1478.40
1.13	2.00	m3	Supplying and filling 20 mm metal for sludge drying bed 1 & 2 including cost of material, labour for filling conveyance etc complete.	/m3	970.20	1940.40
1.14	2.00	m3	Supplying and filling 3mm sand for sludge drying bed 1 & 2 including cost of material, labour for filling conveyance etc complete.	/m3	2330.90	4661.80
1.15	40.00	Nos	Supplying and fixing C.I manhole cover 600 x 600mm heavy duty	/Each	1300.00	52000.00
1.16	2.00	Nos	Supplying and fixing Aluminium ladder	/Each	1500.00	3000.00
1.17	2.00	plants	Timber piling for lateral soil support using coconut stem and slabs			280000.00
1.18			Dewatering the pit at the time of construction			255000.00
1.19			Dewatering the drain well with concrete rings			250000.00
1.20	239	m3	The increase in cost for doing RCC and PCC inside the pit	m3	950.00	227050.00
1.21	200	qntl	Increase in reinforcement work	/qntl	450.00	90000.00
						4400704

RUPEES FOURTY FOUR LAKHS SEVEN HUNDRED AND FOUR ONLY

I/We do here by agree to undertake and execute the above work as per the rate given in this schedule .

FOR OFFICE USE

insertions

Corrections


Over writing

Scoring

Opened by

Witness

Secretary





SECRETARY
 Sree Narayana Gurukulam Charitable Trust
 Perumbavoor - 683 542
 Sree Narayana Gurukulam
 College of Engineering
 Kadayiruppu, Kolenchery-682 311



BIO ENERGY SYSTEM

Consultants / manufacturer of Ecosan Biogas Plant

1st Floor, Room No. 35, Vyapara Bhavan, Bank Road, Calicut - 673 001
Ph: 0495 4050630, Mob: 9447300630, E-mail: nascobiogas@yahoo.com

www.bioenergysystems.in

Consultant Wing of IRTC & KAICO


Approved by: Pollution control board, Suchitwa Mission & ANERT, Govt. of Kerala


16.12.2010

Receipt

Received an amount of Rs.1,00,000.00 (*Rupees: One Lakh Only*) towards the construction of Biogas plant at Boy's Hostel Premises, Sree Narayana gurukulam College of Engineering.

With regards


for Nazir.V.K





PRINCIPAL
Sree Narayana Gurukulam
College of Engineering
Kadayiruppu, Kolenchery-682 311